



Snapshot view of the Onsite Energy LCR (Local Capacity Requirements) Incentives Process:

## Phase 1 – Confirm Eligibility:

Site and SCE Account Verification

(Need Single Copy of SCE Bill)

(See Map for general geographical LCR footprint)



Eligibility Confirmation is usually same day



## Phase 2 – Project Scope Submission to Onsite Energy

Pre-Installation Conditions: LCR program awards incentives on *measured kW* demand reduction during peak hours 2pm – 5pm, Mon – Fri.

\*Please note

- Contractor provides Onsite a fully completed, transparent LE Table/Scope of Work.
- Actual full system watts should be indicated in pre-and post-conditions.
- Savings reductions / incentives are applicable only to lights that are on during the summer hours of **2-5 PM, M-F**, so remember to include if lights are operating on occupancy sensors.
- Full system wattage of the existing and proposed must account for ballast factor (hi-med-low) and occupancy / motion sensors.

- Pictures of existing ballasts and lamps must be included (one picture for each type).
- Areas cooled by HVAC must be noted (Interactive savings are allowed in the LCR Program).
- All proposed product specifications / cut sheets must be included.

## Phase 3 - Pre-Installation Inspection



- Conducted within 2-4 weeks of your submitted project.
- Inspection will verify submitted scope of work, wattages and counts reported by areas.
- Establishes baseline for measurement and verification (M&V).

## Phase 4 – Project Approved to Proceed

(Approximately 45-60 Days from Project Submission)



## Phase 5 – Post-Installation Inspection

- Conducted within 2 weeks after job completion.
- Inspection will verify installation aligns with the submitted scope of work submitted.

- Inspection will include monitoring hourly usage (2 weeks), and wattage readings (statistical sample of total project areas).
- Submitted to SCE for approval by Onsite / Evaluator.

## **Phase 6 - SCE Approval – Approximately 60 Days After Job**

Completion; LCR incentives will be paid 30 days following SCE approval.

